Tender:

Q11997/2026
THE APPOINTMENT OF A CONTRACTOR FOR PAVING BETWEEN ENCLOSURES AT MOKOPANE BCC

Addendum: 01

The updated BOQ: The inclusion of item 1 and item 2 and amended item 4.01 excavation to be 150mm (63m3).

TABEL C2-1

Payment Refers to	Item No.	Description	Unit	Quantity	Rate	Amount
	1	**P & Gs'**	**sum**	**1**	**R**	**R**
	2	**Occupation Health and Safety**	**sum**	**1**	**R**	**R**
	3.00	Removal of old paving				
	3.01	Remove old paving and concrete slab in the selected areas to local municipal dump site.	m2	358	R	R
	4.00	Preparation of area for new paving				
	4.01	Excavate substrate, clay soils to a depth of **150mm** below natural ground level. (Area only has clay soils, no rock)	m3	**63**	R	R
	4.02		m3	84	R	R
	4.03	Fill area with G6 soil and compact to 95% MODAASTHO 200mm.	m3	9	R	R
		Place 20mm river sand over the G6 material.				
	5.00	Paving				
	5.01	Interlinking concrete brick blocks placement.	m2	416	R	R
	5.02	Grout paving after placement with sand.	m3	9	R	R

Payment Refers to	Item No.	Description	Unit	Quantity	Rate	Amount
	6.00	Curbing				
	6.01	Edge all paving with E3 curbing. and haunch and backfill to ground level all paving lines.	m	304	R	R
	6.02	Edge the access points of the paving with mountable curbing haunch and backfill to ground level.	m	23	R	R
	7.00	Site closure				
	7.01	Removal of all waste to municipal dump site.	No.	1	R	R
					Sub Total .	**R**
					Value Added Tax .	**R**
					Grand Total .	**R**

Pricing is to include all costs including labour, materials and equipment.